

FINISH SCHEDULE																
REV.	NO	Ino	ROOMS	FLOORS		PLINTHS		WALLS		CEILINGS		REMARKS	SURFACE			
				BASE	ACC1	ACC2	BASE	ACC1	ACC2	BASE	ACC1			ACC2		
402 - LEVEL 1 - P62																
JT.202.04.23			Vestibule 1										15.4 m²			
JT.202.04.24			Vestibule 2										15.4 m²			
JT.202.04.25			Elevator shaft										26.4 m²			
JT.202.04.26			Pumping STATION										10.6 m²			
JT.202.04.27			Predaction										6.0 m²			
402 - LEVEL 2 - P62																
JT.202.04.28			Entreposage										7.0 m²			
JT.202.04.29			Electrical room										13.5 m²			
JT.202.04.30			Telecom room										21.1 m²			
JT.202.04.31			Water entry room										8.8 m²			
485 - LEVEL 1																
JT.100.00.01			Vestibule - DOM										31.5 m²			
JT.100.00.02			Departure corridor										86.2 m²			
JT.100.00.04			Zone fauteuils roulants vestibule - DOM									2.5 m x 5m (27 juin 2025)	16.4 m²			
JT.100.00.05			Zone fauteuils roulants rampe										7.8 m²			
JT.100.01.01			Vestibule - INTL										31.7 m²			
JT.100.01.02			Departure corridor										86.3 m²			
JT.100.01.04			Zone fauteuils roulants vestibule - INTL										18.2 m²			
JT.100.01.05			Zone fauteuils roulants rampe										13.9 m²			
JT.100.03.01			Vestibule 221										35.0 m²			
JT.100.03.02			Vestibule 223										8.4 m²			
JT.100.03.03			Vestibule 227										35.0 m²			
JT.100.03.04			Vestibule 229										34.8 m²			
JT.200.00.01			Room d'embarquement - DOM									None / painted concrete / acp	1 223.3 m²			
JT.200.00.02			Room d'embarquement - INTL									None / painted concrete / acp	1 209.3 m²			
JT.200.00.04			Corridor WC									None / painted concrete / acp	75.7 m²			
JT.200.00.05			Corridor WC									None / painted concrete / acp	74.3 m²			
JT.201.00.03			Rampe porte 221 - niv1									None / painted concrete / acp	125.5 m²			
JT.201.01.03			Rampe porte 223 - niv1									None / painted concrete / acp	197.3 m²			
JT.201.02.03			Rampe porte 227 - niv1									None / painted concrete / acp	126.9 m²			
JT.201.03.03			Rampe porte 229 - Niv 1									None / painted concrete / acp	126.9 m²			
JT.202.00.01			Departure ramp 227 Lvl.1									None / painted concrete / acp	173.1 m²			
JT.202.00.03			Departure ramp 229									None / painted concrete / acp	169.1 m²			
JT.202.01.01			Departure ramp 221 M.1									None / painted concrete / acp	144.1 m²			
JT.202.01.03			Departure ramp 223 M.1									None / painted concrete / acp	177.6 m²			
JT.202.02.01			Departure corridor tarmac - INTL									None / painted concrete / acp	45.2 m²			
JT.300.00.01			Bureau ASFC									None / acp	18.3 m²			
JT.300.00.02			Room d'entretien									None / acp	12.2 m²			
JT.400.00.01			Commerces INTL									None / painted concrete / acp	58.7 m²			
JT.400.00.02			Entreposage - Commerce INTL									None / acp	16.4 m²			
JT.400.00.03			Machines distributrices									None / painted concrete / acp	48.8 m²			
JT.500.00.01			Toilettes mixtes									None / acp	109.4 m²			
JT.500.00.03			Toilettes mixtes									None / acp	109.4 m²			
JT.500.00.05			Assisted washroom									None / acp	11.1 m²			
JT.500.00.06			Assisted washroom									None / acp	11.1 m²			
JT.500.00.07			Lieu d'attente carin									None / acp	12.3 m²			
JT.500.00.08			Lieu d'attente carin									None / acp	12.8 m²			
JT.500.00.09			Room d'attente									None / acp	9.8 m²			
JT.500.00.10			Room d'attente									None / acp	9.8 m²			
JT.500.00.11			TECHNICAL VOID 1									None / acp	9.7 m²			
JT.500.00.12			TECHNICAL VOID 2									None / acp	3.4 m²			
JT.500.00.13			TECHNICAL VOID 3									None / acp	10.2 m²			
JT.500.00.14			TECHNICAL VOID 4									None / acp	2.8 m²			
JT.500.00.15			TECHNICAL VOID 5									None / acp	8.7 m²			
JT.500.00.16			TECHNICAL VOID 6									None / acp	10.2 m²			
JT.500.00.17			TECHNICAL VOID 7									None / acp	2.8 m²			
JT.500.00.18			TECHNICAL VOID 8									None / acp	2.8 m²			
JT.500.01.01			Washroom - employee									NOT basin accessible (croquis 14 sept.)	3.0 m²			
JT.500.01.02			Washroom - employee									NOT basin accessible (croquis 14 sept.)	3.0 m²			
JT.500.01.03			Accessible washroom - employee									None / acp	10.3 m²			
JT.500.02.01			Concierge									None / acp	4.8 m²			
JT.500.02.02			Concierge									None / acp	4.8 m²			
JT.600.00.01			Telecom room - main									5m x 7m, Adjacent elec. room (3 July 2025) 8m MAX distance between Telecom (28 seven 2025)	40.2 m²			
JT.600.00.02			Telecom room									None / painted concrete / acp	28.0 m²			
JT.600.00.03			Electrical room									None / painted concrete / acp	19.3 m²			
JT.600.00.04			Telecom room									None / painted concrete / acp	28.0 m²			
JT.600.00.05			Electrical room									None / painted concrete / acp	19.3 m²			
JT.600.00.07			Telecom room									None / painted concrete / acp	28.6 m²			
JT.600.00.08			Electrical room									None / painted concrete / acp	18.1 m²			
JT.600.00.09			Telecom room									None / painted concrete / acp	39.3 m²			
JT.600.00.10			Electrical room									None / painted concrete / acp	22.4 m²			
JT.600.00.11			Main electrical entrance									None / painted concrete / acp	92.2 m²			
JT.600.00.12			Electrical room									8m MAX distance between Room Electrical (28 seven 2025)	14.9 m²			
JT.600.00.13			Water entry room									3m x 7m (12 august), 4m x 7m (2m 2025)	21.2 m²			
JT.600.00.14			Electrical room									3m x 4m (16 seven. 2025)	18.4 m²			
JT.600.00.15			Local entreposage - maintenance ADM									3.8m x 5m (27 juin 2025)	22.1 m²			
JT.600.00.17			Concierge - maintenance sanitary (equipment)									3.8m x 5m (27 juin 2025)	11.8 m²			
JT.600.00.25			Electrical room - INTL									None / painted concrete / acp	20.8 m²			
JT.600.00.28			Predaction									1.5m x 2m (16 seven. 2025)	2.6 m²			
JT.600.00.29			PROTECTION - FIRE									1.5m x 2m (29 mai 2025)	4.9 m²			
JT.600.00.32			Waste room									None / painted concrete / acp	13.4 m²			
JT.600.00.34			Telecom room									3m x 3m, Adjacent elec. room (3 July 2025)	22.4 m²			
JT.600.00.35			Technical room - access control									None / painted concrete / acp	91.4 m²			
JT.600.00.44			Predaction room									None / painted concrete / acp	6.5 m²			
JT.600.00.48			Local ventilation/humidificateur									None / painted concrete / acp	16.6 m²			
JT.600.00.49			Technical closet - access control									3pi x 10pi (14oct)	3.0 m²			
JT.600.00.50			Technical room - access control									None / painted concrete / acp	12.8 m²			
JT.600.00.51			Local entreposage 4 - DOM									None / painted concrete / acp	6.6 m²			
JT.600.00.52			Local entreposage 5 - INTL									None / painted concrete / acp	5.2 m²			
JT.600.01.01			Entreposage compagnie									13m(19.20m), 2m x 5m (27 juin 2025)	9.6 m²			
JT.800.01.01			Employee break room - ADM									5 pers. + some security agents (25 août 2025)	26.5 m²			
JT.800.01.02			Employee break room - companies airlines									14 pers. to this peak (25 août 2025)	36.1 m²			
JT.800.01.03			Condor service									5.4m x 5m (27 juin 2025)	33.5 m²			
JT.800.01.04			Condor service									5.4m x 5m (27 juin 2025)	39.5 m²			
JT.800.01.07			Condor service									None / painted concrete / acp	14.4 m²			
JT.800.01.10			Back vestibule - DOM									None / painted concrete / acp	3.6 m²			
JT.800.01.11			Back vestibule - INTL									None / painted concrete / acp	4.5 m²			
JT.800.01.12			Service corridor 221									None / painted concrete / acp	72.4 m²			
JT.800.01.13			Wheelchair area 221									None / painted concrete / acp	36.0 m²			
JT.800.01.14			Service corridor 227									None / painted concrete / acp	72.7 m²			

FINISH SCHEDULE													
REV.	NO	PROG.	ROOMS	FLOORS		PLINTHS		HALLS		CEILING		REMARKS	SURFACE
				BASE	ACCT	ACCT	BASE	ACCT	ACCT	BASE	ACCT		
	JT.800.01.15		Wheelchair area 227	none		ca1				none / painted concrete / acp			35.9 m²
	JT.800.01.16		Service corridor 229	none		ca1		gyp		none / painted concrete / acp			70.8 m²
	JT.800.01.17		Wheelchair area 229	none		ca1		gyp		none / painted concrete / acp			35.9 m²
	JT.800.01.18		Corridor service	none		ca1		gyp		none / painted concrete / acp			38.6 m²
	JT.800.01.19		Corridor service	none		ca1		gyp		none / painted concrete / acp			33.7 m²
	JT.900.00.01		Employee break room - ramp agents	tp1		acp	oc1	gyp	oc1	gyp	oc1	8.5m x 4.2m (27 Jan 2025)	38.8 m²
	JT.900.00.02		Modification room - ramp agents	tp1		acp	oc1	gyp	oc1	gyp	oc1	5m x 3m (27 Jan 2025)	11.5 m²
	JT.X00.00.00A		ESCALUER 4										17.5 m²
	JT.X00.00.00B		ESCALUER 5										18.3 m²
	JT.X00.00.XX		ESCALUER 1										19.6 m²
	JT.X00.00.YY		ESCALUER 2										19.0 m²
	JT.X00.00.ZZ		ESCALUER 3										18.9 m²
485	LEVEL 2												
	JT.100.00.02		Elevated roadway 227	ti1		ti2		gyp	(scepty)	gyp	ci1		347.3 m²
	JT.100.00.06		Elevated roadway 229	ti1		ti2		gyp	(scepty)	gyp	ci1		550.0 m²
	JT.100.00.08		Corridor porte 223	ti1		ti2		gyp	(scepty)	gyp	ci1		76.7 m²
	JT.100.01.03		Departure elevated roadway 221	ti1		ti2		ti1		gyp	ci1		336.8 m²
	JT.201.00.01		Porte 221a	ti1		ti2		ti1	(scepty)	gyp	ci1		47.0 m²
	JT.201.00.02		Porte 221b	ti1		ti2		ti1	(scepty)	gyp	ci1		101.6 m²
	JT.201.00.04		Rampe porte 221 - niv2	ti1		ti2		ti1	(scepty)	gyp	ci1		196.0 m²
	JT.201.01.01		Porte 223a	ti1		ti2		ti1	(scepty)	gyp	ci1		32.2 m²
	JT.201.01.02		Porte 223b	ti1		ti2		ti1	(scepty)	gyp	ci1		111.2 m²
	JT.201.01.04		Rampe porte 223 - niv2	ti1		ti2		ti1	(scepty)	gyp	ci1		160.3 m²
	JT.201.02.01		Porte 227a	ti1		ti2		ti1	(scepty)	gyp	ci1		54.2 m²
	JT.201.02.02		Porte 227b	ti1		ti2		ti1	(scepty)	gyp	ci1		86.7 m²
	JT.201.02.04		Rampe porte 227 - niv2	ti1		ti2		ti1	(scepty)	gyp	ci1		109.2 m²
	JT.201.03.01		Porte 229a	ti1		ti2		ti1	(scepty)	gyp	ci1		65.4 m²
	JT.201.03.02		Porte 229b	ti1		ti2		ti1	(scepty)	gyp	ci1		99.3 m²
	JT.201.03.04		Rampe porte 229 - Niv 2	ti1		ti2		ti1	(scepty)	gyp	ci1		175.5 m²
	JT.202.00.02		Departure ramp 227 Lvl 2	ti1		ti2		ti1	(scepty)	gyp	ci1		17.1 m²
	JT.202.01.02		Departure ramp 221 -niv2	ti1		ti2		ti1	(scepty)	gyp	ci1		117.8 m²
	JT.202.01.04		Departure ramp 223 Lvl 2	ti1		ti2		ti1	(scepty)	gyp	ci1		9.8 m²