GENERAL NOTES

1. NO DIMENSION SHALL BE TAKEN OR MEASURED DIRECTLY FROM THE DRAWINGS.
2. ALL DIMENSIONS RELATIVE TO EXISTING CONDITIONS ARE APPROXIMATE, THEY ARE FOR INDICATIVE PURPOSES ONLY AND MUST BE VERIFIED ON SITE BY THE CONTRACTOR (WHETHER OR NOT THEY SHOW THE NOTATION "±"). SOME ADJUSTMENTS MAY BE REQUIRED DEPENDING ON EXISTING CONDITIONS OR CHANTIER.
3. BEFORE PROCEEDING WITH THE EXECUTION OF THE WORK, THE CONTRACTOR MUST VERIFY ALL DIMENSIONS AND CONDITIONS ON SITE. HE MUST IMMEDIATELY NOTIFY THE ARCHITECT AND THE PROFESSIONALS OF ANY CONTRADICTION OR DISCREPANCY.
4. THE SHADED AREA, OR GRAY AREA ON THE ARCHITECTURAL DRAWINGS IS INDICATED FOR INDICATIVE PURPOSES ONLY AND TO FACILITATE THE READING OF DOCUMENTS BY THE VARIOUS STAKEHOLDERS. IT DOES NOT LIMIT THE SCOPE OF WORK. THUS, AN INTERVENTION OR NOTE LOCATED IN THIS SHADED OR GRAYED AREA IS PART INTEGRAL PART OF THE WORK TO BE DONE IN THIS PROJECT.
5. AS SUCH, ALL ELECTRICAL AND MECHANICAL CONDUITS ARE RECESSED.
6. ALL CONDUITS PASSING THROUGH PARTITIONS, CEILINGS AND/OR SLABS HAVING A FIRE RESISTANCE RATING, MUST BE SEALED WITH A ENSEMBLE FIREBREAK / SMOKE BARRIER (SCELLANT AND ISOLANT IGNIFUGES CONTINUS) EN ACCORDING TO THE REQUIRED FIRE RESISTANCE RATING. ALL TO ENSURE THE INTEGRITY OF THESE SEPARATIONS.
7. THE COLORS OF THE FINISHES SHALL BE AT THE CHOICE OF THE ARCHITECT.
8. ALL PARTITIONS SHALL BE CONSTRUCTED FROM SLAB TO SLAB, EXCEPT WHERE INDICATED AUTREMENT.
9. PROVIDE BLOCKING FOR ALL ACCESSORIES AND EQUIPMENT IDENTIFIED ON THE PLANS OR IN THE SPECIFICATIONS.
10. SPACE AT LEAST 150 mm BETWEEN RECESSED BOXES AND/OR CABINETS ON BOTH SIDES IN PARTITIONS WITH FIRE RESISTANCE RATING.
11. INSIDE THE BUILDING, DOORS AND FRAMES LOCATED IN A SEPARATION FIRE-RATED DOIVENT AVOIR LE DEGRÉ PARE-FLAMME CORRESPONDANT AUX EXIGENCES OF THE CODE IN FORCE (TABLE 3.1.8.4). ALL OPENINGS (WITHOUT EXCEPTION) CONTAINED IN SUCH A SEPARATION MUST BE SEALED BY MEANS OF A APPROVED FIRE-STOP ASSEMBLY HAVING THE REQUIRED FIRE RESISTANCE RATING. FOR EXAMPLE, THE PERIMETERS OF DUCTS, PIPES, ELECTRICAL WIRES, ETC.
12. THE GENERAL NOTES AND ANNOTATIONS ON THE DRAWINGS ARE COMPLEMENTARY. IF THERE IS AMBIGUITY BETWEEN THEM, THE MORE STRINGENT NOTE SHALL TAKE PRECEDENCE. IN BESOIN, CONSULTER L'ARCHITECTE.

GENERAL NOTES / PLANS

1. AS SUCH, THE DIMENSIONS OF INTERIOR GYPSUM PARTITIONS MUST BE READ AS BEING THE CENTER OF THE PARTITION. THE DIMENSIONS OF ANGLED PARTITIONS BY REPORT AUX AXES SONT DONNÉES SUR LES COINS, EN GÉNÉRAL.
2. AS SUCH, POSITION OF DOOR FRAMES: INSTALL LA FACE INTERNE DU CADRE A 150 mm DU WALL WALL (UNLESS OTHERWISE INDICATED). 150mm
3. AS SUCH, THE NUMBER IDENTIFYING EACH DOOR CORRESPONDS TO THE ROOM NUMBER TO WHICH THIS DOOR PROVIDES ACCESS.
4. THE OPENING DIMENSIONS INDICATED REPRESENT THE OPENINGS BRUTES REQUISES.
5. FOR TYPICAL ENVELOPE ELEMENTS: SEE SHEET A-501.
6. FOR EXTERIOR SOFFIT TYPES: SEE SHEET A-501.
7. FOR PARTITION TYPES: SEE SHEET A-701.
8. FOR ENLARGED PLANS OF TOILETS: SEE SHEETS SERIES A-600.
9. FOR ENLARGED PLANS OF STAIRS AND VERTICAL TRANSPORTATION: SEE SHEETS SERIES A-450.
10. FOR DETAILS OF LINEN AND WASTE CHUTES: SEE SHEETS SERIES A-450.
11. FOR FURNITURE DRAWINGS: SEE SHEETS SERIES A-800

GENERAL NOTES / CEILINGS

1. AS SUCH, ALL SUSPENDED CEILINGS ARE TYPE [TO BE COMPLETED] SEE FINISH SCHEDULE FOR TYPE OF SUSPENDED CEILING.
2. SIC, THE GRIDS OF ACOUSTIC TILE CEILINGS ARE CENTERED IN BOTH DIRECTIONS WITHIN A ROOM.
3. AS SUCH, THE LIGHTS ARE CENTERED IN BOTH DIRECTIONS IN THE ACOUSTIC TILE OR IN THE SPACE AND THE ARE ALIGNED ON ONE SIDE OF THE GRID.
4. SIC, LA HEIGHT DES PLAFONDS EST DEJÀ [COMPLÉTER].
5. THE FINAL POSITION OF THE SUPPORT STRUCTURES FOR EQUIPMENT FOR THE ANCHORING OF ARTICULATED ARMS MUST BE COORDINATED WITH THE THE SITE ACCORDING TO MANUFACTURER'S RECOMMENDATIONS.
6. AS SUCH, THE POSITION OF VENTILATION GRILLES FOR SUPPLY AND RETURN MUST ALWAYS BE 150 mm FROM WALLS, OR OTHER ELEMENTS ADJACENTS.

GENERAL NOTES / ROOFS

1. FOR LEVELS OF CONCRETE AND STEEL STRUCTURES: SEE DOCUMENTS ENGINEERING DOCUMENTS.
2. FOR THE LOCATION OF MECHANICAL AND ELECTRICAL EQUIPMENT, AND FOR THE EXACT NUMBER OF ROOF BASES REQUIRED: SEE ENGINEERING DOCUMENTS.
3. FOR ROOFING TYPES (TT-...): SEE SHEET A-501.

GENERAL NOTES / ELEVATIONS

1. THE DIMENSIONS INDICATED FOR THE CURTAIN WALL ARE TAKEN FROM THE CENTER OF THE MULLION AND/OR FLOOR LEVEL.
2. THE OPENING DIMENSIONS INDICATED REPRESENT THE OUVERTURES BRUTES REQUISES.

LEGENDS AND SYMBOLS

PLANS

- EXISTING PORTION
- BACKFILLED SOIL (SEE ENGINEERING DOCUMENTS)
- XXX1 — NEW STRUCTURAL AXIS
- XXX1 — EXISTING STRUCTURAL AXIS
- 0 A-000 — ELEVATION REFERENCE
- TYP. 0 A-000 — DETAIL OR PLAN REFERENCE
- 0 A-000 — SECTION REFERENCE
- NEW DOOR AND FRAME
- EXISTING DOOR AND FRAME
- EXISTING DOOR AND FRAME TO BE DEMOLISHED
- NEW PARTITION
- NEW SHIELDED PARTITION
- EXISTING PARTITION TO BE RETAINED
- EXISTING PARTITION TO BE DEMOLISHED
- TEMPORARY CONSTRUCTION PARTITION (SEE SPECIFICATIONS)
- CONCRETE BLOCK PARTITION
- 0 HOUR FIRE SEPARATION
- 45 MIN FIRE SEPARATION
- 1 HOUR FIRE SEPARATION
- 1 1/2 HOUR FIRE SEPARATION
- 2 HOUR FIRE SEPARATION
- 0x — PARTITION AND TYPE OF PARTITION (VOIR FEUILLE A-701) THE ARROW INDICATES THE BEGINNING OF THE DESCRIPTION
- 0x HT XXXX — LOW PARTITION WITH REQUIRED HEIGHT
- CTR — BRACING (SEE ENGINEERING DOCUMENTS)

ABBREVIATED NAME	THESE DOCUMENTS MUST NOT BE
0000.00.00	ROOM NUMBERING
(Superficie requise) Actual Area	SUPERFICIES
	IDENTIFICATION OF SPECIFIC LAYOUT NOTE (A), RENOVATION (R) AND DEMOLITION (D)
JT.400.00.02A1	IDENTIFICATION OF DOORS, GLAZED PARTITIONS AND VARIOUS OPENINGS
M000	FURNITURE IDENTIFICATION
a001	IDENTIFICATION OF TYPES OF TOILET ACCESSORIES AND MISCELLANEOUS
	IDENTIFICATION OF BMS OR IT EQUIPMENT
E000	IDENTIFICATION OF SPECIALIZED EQUIPMENT
A Z01	REVISION NUMBERING
00.000	FLOOR LEVEL
LP	PAINT LIMIT
	NEW ELEMENT INSTALLED IN EXTENSION OF THE EXISTING AND/OR REQUIRED ALIGNMENT BETWEEN TWO ELEMENTS
EH	UP
EB	DOWN
	GRILL GRATTE-PIEDS
	MISCELLANEOUS PLUMBING FIXTURES (SEE ENGINEERING DOCUMENTS)
PAL PAL	CORNER GUARD (TYPE...)
PM PC PM PC	WALL PROTECTION (TYPE...) OR BUMPER (TYPE...)
PM	WALL COVERING (TYPE...)

BLOCKING

THE BLOCKING IDENTIFIED ON THE DRAWINGS AND ON THE EQUIPMENT AND ACCESSORIES LISTS ARE THE BLOCKING REQUIRED FOR EQUIPMENT SUPPLIED (OR SUPPLIED AND INSTALLED) BY THE OWNER. THIS BLOCKING IS IDENTIFIED ON THE DRAWINGS WITH THE ABBREVIATION "RVX". THE CONTRACTOR MUST SUPPLY AND INSTALL THIS BLOCKING AND VALIDATE ITS FINAL POSITIONING WITH THE OWNER ON SITE BEFORE ITS INSTALLATION.

ON THE OTHER HAND, IT IS THE CONTRACTOR'S RESPONSIBILITY TO SUPPLY AND INSTALL ALL OTHER BLOCKING REQUIRED FOR ALL EQUIPMENT, ACCESSORIES OR ALL OTHER ELEMENTS TO BE INTEGRATED INTO THE WORK PROVIDED IN THE DOCUMENTS. THE LATTER ARE NOT POSITIONED ON THE DRAWINGS AND THE CONTRACTOR MUST COORDINATE WITH EACH OF OF THEIR SUBCONTRACTORS FOR THEIR DIMENSIONS AND POSITIONING.

RVX	BLOCKING
TYPE 1 (RV1):	PLYWOOD BLOCKING 19 mm, 600 mm HIGH X 800 mm LONG TO BE INSTALLED BETWEEN STUDS (CENTER AT 1500 mm HIGH)
TYPE 2 (RV2):	PLYWOOD BLOCKING 19 mm TO BE INSTALLED BETWEEN THE STUDS FROM 400 mm FROM FLOOR TO 2440 mm HIGH
TYPE 3 (RV3):	PLYWOOD BLOCKING 19 mm X 1200 HIGH TO BE INSTALLED ENTRE LES COLOMBAGES À 305 mm DU FLOOR
TYPE 4 (RV4):	PLYWOOD BLOCKING 19 mm, 600 mm HIGH X 600 mm LONG TO BE INSTALLED BETWEEN STUDS (CENTER AT 1500 mm FROM FLOOR)

SITE LAYOUT AND LANDSCAPING

- EXISTING CONSTRUCTION
- NEW CONSTRUCTION OU EXPANSION
- GROUNDCOVER / PLANTING BED (SEE LANDSCAPE)
- LAWN
- ORIENTATION NORD
- SENS CIRCULATION
- BUILDING ENTRANCE
- WATER FOUNTAIN STAND
- STREET LIGHT (SEE ENGINEERING DOCUMENTS)
- PROPERTY LINE
- SUMP
- EXISTING TREE RETAINED / TO BE REMOVED (SEE LANDSCAPE)
- NEW TREE (SEE LANDSCAPE)
- SHRUBS (SEE LANDSCAPE)

PLAFONDS

- EXISTING PORTION
- GYPSUM CEILING
- SUSPENDED ACOUSTIC TILE CEILING
- WOOD CEILING
- FIRE-RATED BOX IN PLENUM WITH 1HR FRR
- FIRE-RATED BOX IN PLENUM WITH 2HR FRR
- CEILING AREA TO BE REMOVED AND REINSTALLED FOLLOWING WORK
- ZONE OÙ UN SYSTÈME OF SUPPORTS INTERMÉDIAIRE FOR SUSPENDED CEILING ANCHORING MUST BE INSTALLED
- SUSPENDED LIGHT FIXTURE (SEE ENGINEERING DOCUMENTS)
- RECESSED LIGHT FIXTURES (SEE ENGINEERING DOCUMENTS)
- RADIANT HEATING CEILING (SEE ENGINEERING DOCUMENTS)
- WALL SCONCE (SEE ENGINEERING DOCUMENTS)
- RECESSED LIGHT FIXTURE (SEE ENGINEERING DOCUMENTS)
- RETURN (SEE ENGINEERING DOCUMENTS)
- RETURN (SEE ENGINEERING DOCUMENTS)
- DIFFUSER (SEE ENGINEERING DOCUMENTS)
- POUTRELLES (STRUCTURE APPARENTE)
- PARTITION TO STRUCTURE
- PARTITION / GLAZED PARTITION TO CEILING
- SPRINKLER (SEE ENGINEERING DOCUMENTS)
- TSD — DOUBLE SOLAR SCREENS AND SCREEN CLOSURE PLATE
- HT 0000 — FINISHED CEILING HEIGHT
- X00 — EXTERIOR SOFFIT TYPE (SEE ASSEMBLIES SECTION ENVELOPE FOR ABBREVIATIONS)

ELEVATIONS

- EXISTING PORTION
- 2 — EXPOSED CONCRETE WALL
- LS — STRUCTURAL LINTEL (SEE ENGINEERING DOCUMENTS)
- LEVEL 000.000 — LEVEL
- ALIGNED
- 0 A-000 — WALL SECTION IN BACKGROUND
- X00 — ENVELOPE ASSEMBLY TYPE (SEE SECTION ENVELOPE ASSEMBLIES FOR ABBREVIATIONS)
- F00 — WINDOW IDENTIFICATION

ROOF

- EXISTING PORTION
- TAPERED INSULATION
- MEMBRANE
- METAL FLASHING
- NIV1 / BD1 TT1 — IDENTIFICATION OF ROOF LEVEL AND DRAINAGE BASIN NUMBER ROOF IDENTIFICATION
- SLOPE 10%. — ROOF SLOPE (SEE ABBREVIATIONS SECTION)
- 00 DT — DRAIN OF ROOF (VOIR DÉTAILS TYPIQUES SERIES A-590)
- EV — ÉVENT OF PLOMBERIE, INCLUANT MANCHON PRÉFABRIQUÉ AND ISOLÉ (SEE TYPICAL DETAILS AND SEE ENGINEERING DOCUMENTS)

INTERIOR ELEVATIONS AND FURNITURE

- FINISHED BACKSPLASH PLASTIC LAMINATE
- A — MEDICAL AIR (SEE ENGINEERING DOCUMENTS)
- O — OXYGEN (SEE ENGINEERING DOCUMENTS)
- V — MEDICAL VACUUM (SEE ENGINEERING DOCUMENTS)
- SWITCH (SEE ENGINEERING DOCUMENTS)
- INTERCOM (SEE ENGINEERING DOCUMENTS)
- NURSE CALL (SEE ENGINEERING DOCUMENTS)
- ELECTRICAL OUTLET (SEE ENGINEERING DOCUMENTS)
- DATA / TELEPHONE OUTLET (SEE ENGINEERING DOCUMENTS)
- LOCK

MATERIALS TERMS

ac	steel	pia	pierre artificielle
aci	stainless steel	pbé	concrete panel
al	aluminum	pbo	wood strip parquet flooring
ar	ardoise	pfs	laminate floating floor
asp	asphalt	pi	stone
		pla	plaster
bbé	concrete block	pmé	metal decking
bé	concrete	prt	thermosetting resin panel
bo	wood	ps	plastic laminate
br	brick	pt	stretched ceiling
bv	varnished concrete block	pvb	concrete paver
bz	bronze		
		rm	wall covering
ca	caoutchouc	rv	vinyl-coated fabric covering
cc	ceramic tile		
cf	sheet rubber	st	stuc
cg	granite tile		
ci	carreaux insonorisants	ta	tapis
cmn	metal tile ceilings	tc	carpet tile
cp	plywood	te	terrazzo
cr	cement stucco	ti	tissu
cs	composite solide (Corian)	tm	titanium
ct	terrazzo tile	tn	travertin
cu	cuivre	tep	plastic-bonded terrazzo
cv	glass tile	tr	terracotta
ea	enduit acoustique	v	glass
ebé	precast concrete element	va	wired glass
ec	cement plaster	vac	verre acoustique
eg/r	gypsum plaster	vc	vinyl tile
ei	enduit ignifuge	vcr	crystallized glass
iht	enduit acrylique	vf	vinyl sheet
ep	epoxy floor coating	vi	vinyle
ex	epoxy wall and ceiling coating	vs	safety glass
fdv	fiberglass		
gyp	premolded gypsum		
gr	granit		
gyv	vinyl-covered gypsum		
gy	gypsum		
if	isolant fibre cellulosique		
ig	ignifuge		
im	waterproofing		
iv	spray foam insulation		
lbo	wood strips		
lg	cork		
li	linoleum		
lm	metal filler strip		
MAIL	metal stat ceiling		
ma	marble		
MEASURED	expanded metal		
MEASURED	metal		
mdf	MDF		
ml	melamine		
mm	membrane		
MEASURED	perforated metal		
mq	marquetterie		

FINISHES

NOTE: THE "LETTER" CODE OF FINISHES IS ADDED TO THE MATERIAL TERMS DESCRIBED ABOVE TO DEFINE THE FINISH

A	anodized	B	to be retained and relocated
D	durcisseur et/ou scelleur	C	to be retained
E	epoxy paint	R	to be refurbished
F	baked enamel	X	to be removed / demolished
G	textured paint		
H	lime plaster		
J	sandblasted		
K	plastic laminate		
L	poli		
M	membrane		
N	prepainted		
O	oxidized		
P	paint		
Q	colored sealer		
S	scelleur		
T	stain and varnish		
U	fini Duranar		
V	varnish		
W	peinture pare-vapeur		
Y	vinyle		
Z	tinned		

FINISH LEGENDS

- GRID START
- Fn# — FRAME AND DOOR (IF STEEL) TO BE PAINTED COLOR xx (EXCEPT STAINLESS STEEL)
- Pn# — ACCENT WALL TO BE PAINTED COLOR xx
- EXISTING PORTION
- xx0 — CLADDING OF ... xx0
- bé5 — SEALED CONCRETE bé5
- bé0 — HARDENED CONCRETE
- vc1 — VINYL TILE FLOORING VC1
- mm1 — MEMBRANE mm1
- xx5 — CLADDING OF ... xx5
- xx6 — CLADDING OF ... xx6
- xx7 — CLADDING OF ... xx7
- li1 — LINOLEUM li1
- xx9 — CLADDING OF ... xx0
- tc1 — REVÊTEMENT OF SOL OF CARPET EN CARREAU tc1
- ep1 — EPOXY FLOORING ep1
- xx — CLADDING OF ... xx0
- xx13 — CLADDING OF ... xx13
- xx14 — CLADDING OF ... xx14
- cc1 — CERAMIC TILE FLOORING cc1
- cc1.1 — CERAMIC TILE FLOORING cc1.1

ASSEMBLIES OR ENVELOPE MATERIALS

NOTE: THE IDENTIFICATION (TYPE...) INDICATES THAT ONE OR MORE NUMBERS ARE ASSIGNED TO THIS ELEMENT TO DIFFERENTIATE IT.

BAP...	BASE ANCHOR PONCTUELLE LIGNE OF VIE (DE TYPE...)
BBO...	BASE FOR DAVIT (TYPE...)
BLV...	BASE FOR ANCHOR LIGNE OF VIE (DE TYPE...)
BS-	SUNSHADE (TYPE...)
F-	WINDOW (TYPE...)
M-	WALL (TYPE...)
MF-	FOUNDATION WALL (TYPE...)
MR...	CURTAIN WALL (TYPE...)
PAR-	PARAPET (TYPE...)
PAL-	ALUMINUM PANEL (TYPE...)
PE-	LOUVERS (TYPE...)
PF-	FRENCH DOOR (TYPE...)
PL-	FLOOR (TYPE...)
PMI-	INSULATED METAL PANEL (TYPE...)
RB...	EXTERIOR BRICK CLADDING (TYPE...)
RME-	METAL CLADDING (TYPE...)
S-	SOFFIT (TYPE...)
SM-	METAL FLASHING (TYPE...)
TT-	ROOF (TYPE...)
TY...	TYMPANUM PANEL (TYPE...)
V...	GLASS (TYPE...)
VT...	GLASS TYMPANUM PANEL (TYPE...)

VARIOUS DRAWING ABBREVIATIONS

NOTE: THE IDENTIFICATION (TYPE...) INDICATES THAT ONE OR MORE NUMBERS ARE ASSIGNED TO THIS ELEMENT TO DIFFERENTIATE IT.

ABA	ABAQUE
AEE	APPAREIL D'ÉCLAIRAGE ENCASTRÉ (NON EXHAUSTIF, SEE DOCUMENTS D'INGÉNIERIE)
AES	APPAREIL D'ÉCLAIRAGE SURFACE (NON EXHAUSTIF, SEE DOCUMENTS D'INGÉNIERIE)
ANC	ANCHORING
ARB	ARBRE, ARBUSTE, HEDGE
ARM	ARMOIRE
ARROS	EXIT D-ARROSAGE
AS	FLOOR DRAIN
ASC	ELEVATOR
ASP	ASPHALT
BA	BOYAU D'ARROSAGE
BC	BASE FOR FIREPLACE
BD...	DRAINAGE BASIN (TYPE...)
BF	FIRE HYDRANT (NON-EXHAUSTIVE, SEE ENGINEERING DOCUMENTS)
BFI	BOULARD FIXE FLEXIBLE
BFL	FLEXIBLE BIKE LANE TYPE POST
BO	WOOD PANEL (SOLID OR CELLULOSE)
BOL	BOULARD
BOP	DOOR OPERATOR BUTTON
BOT	TORREFIED WOOD STRIP CLADDING
CAL	CALIBRE
CCF	COMPARTIMENTATION FIRE-RATED
CDS	CAMERA OF SURVEILLANCE (NON EXHAUSTIF, SEE DOCUMENTS D'INGÉNIERIE)
CGM	MEDICAL GAS CABINET (VALVES, CONTROLS)
CLOBAS	LOW PARTITION
CM	CLOCK
COPEN	COUNTER SLOPE
CRM	COFFRET OF TAP WITH MANOMÈTRES (NON EXHAUSTIF, SEE DOCUMENTS ENGINEERING DOCUMENTS)
CTR	BRACING (NON-EXHAUSTIVE, SEE ENGINEERING DOCUMENTS)
DA	NIVEAU DESSUS D'ACIER
DAL	DALLAGE / PAVÉ
DO	OPENING DEVICE
DP	DRAIN OF FLOOR (NON EXHAUSTIF, SEE DOCUMENTS D'INGÉNIERIE)
DRF	FIRE RESISTANCE RATING
DT	ROOF DRAIN
OF THE	EMERGENCY SHOWER (NON-EXHAUSTIVE, SEE ENGINEERING DOCUMENTS)
EAT	ROOF ACCESS LADDER
EB	DOWN
ECL	LIGHTING
EH	UP
EM	MECHANICAL EQUIPMENT OR UNIT
EPS	FIRE EXTINGUISHER PORTATIF EN SURFACE (NON EXHAUSTIF, SEE DOCUMENTS D'INGÉNIERIE)
EPE	FIRE EXTINGUISHER PORTATIF ENCASTRÉ (NON EXHAUSTIF, SEE DOCUMENTS D'INGÉNIERIE)
ESC	STAIRCASE
ETAG	SHELVING
EV	ROOF VENT
EVAC	EXHAUST (MECHANICAL)
EXT	EXTERIOR
F.A. = P.S.	FACE OF L'ACIER = FACE PANNEAU OF SUPPORT
F.B.	FACE OF CONCRETE
F.E.	FACE OF SHOULDER
FE	DRINKING FOUNTAIN (NON-EXHAUSTIVE, SEE ENGINEERING DOCUMENTS)
FIN	FINISH
FJ	FAUX-JOINT
F.L.L.	FACE OF RAIL OR TRANSOM LINE
F.P.M.I.	FACE OF INSULATED METAL PANEL
F.R.M.	FACE OF METAL CLADDING
F.V.	FACE OF GLASS
FV...	BLOCKING (TYPE...)
GALV	GALVANIZED
GC...	GUARDRAIL (TYPE...)
GGP...	WALK-OFF GRILL (TYPE...)
GM	GAZ MEDICAUX
GRAV	GRAVER
HC	OUT OF CONTRACT
HT	CEILING HEIGHT
HP	SPEAKER (NON-EXHAUSTIVE, SEE ENGINEERING DOCUMENTS)
IN	SWITCH (NON-EXHAUSTIVE, SEE ENGINEERING DOCUMENTS)
INT	INTERIOR
INV	INVERSE
JC	CONTROL JOINT
JCC	COMPARTMENTED CONTROL JOINT
JO...	EXPANSION JOINT COVER (TYPE...)
JOM...	WALL EXPANSION JOINT COVER (TYPE...)
JOME...	EXTERIOR EXPANSION JOINT COVER (TYPE...)
JOP...	CEILING EXPANSION JOINT COVER (TYPE...)
JSF...	FIRE BARRIER FOR EXPANSION JOINTS
JSIL	SILICONE JOINT (CURTAIN WALLS)
LC	CARD READER
LL	FREE LINTEL
LP	PAINT LIMIT
LPR	CEILING-MOUNTED PATIENT LIFT
LS	STRUCTURAL LINTEL
LY	EYEWASH STATION (NON-EXHAUSTIVE, SEE ENGINEERING DOCUMENTS)
MC...	HANDRAIL (TYPE...)
MIR	MIRROR
NA	NOT APPLICABLE
NIV	LEVEL
OB	ROUGH OPENING
OD	SLAB OPENING
OF	FINISHED OPENING
Pv%	SLOPE (AND %)
Pv/%	SLOPE BY TAPERED INSULATION (AND %)
PS/%	STRUCTURAL SLOPE (AND %)
PA...	CORNER GUARD (TYPE...)
PAA	PANNEAU AMOVIBLE
PAC	PANNEAU ACOUSTIQUE
PAE...	CORNER END-GUARD (TYPE...)
PAG	MEDICAL GAS ALARM PANEL
PAM	PANNEAU MIR
PC	BUMPER (TYPE...)
PCO	PRISE OF COURANT (NON EXHAUSTIF, SEE DOCUMENTS D'INGÉNIERIE)
PEL	ELECTRICAL PANEL (NON-EXHAUSTIVE, SEE ENGINEERING DOCUMENTS)
PAF	PANNEAU FIXE
PF	PASSE-FILS
PGAR	GARAGE DOOR
PH	POINT HAUT
PM...	WALL PROTECTION (TYPE...)
PR	NETWORK OUTLET (NON-EXHAUSTIVE, SEE ENGINEERING DOCUMENTS)
PV	VAPOR BARRIER
RA...	METAL SHELVING FOR LIBRARY (TYPE...)
RET	MAGNETIC HOLD-OPEN
RETO	MAGNETIC HOLD-OPEN OPENING
REV	REVISION
RM...	WALL COVERING (TYPE...)
RSI	IV TRACK
RS	IV TRACK
SA	STRUCTURE APPARENTE
SCF	SEPARATION FIRE-RATED
SIC	UNLESS OTHERWISE SPECIFIED
SIM	SIMILAR
T	TIROIR
TAA	TRAPPE D ACCES ARCHITECTURALE
TAB...	BULLETIN BOARD (TYPE...)
TABL	SHELF
TAC	ACCESS HATCH (NON-EXHAUSTIVE, SEE ENGINEERING DOCUMENTS)
TCR...	CHALKBOARD (TYPE...)
TEL	TELEPHONE
TF	FILE DRAWER
TB...	WHITEBOARD (TYPE...)
TFL	FLUORESCENT
TOM	MOTORIZED BLACKOUT SHADE
TP	OVERFLOW / GARGOYLE
TS	TOILE SOLAIRE
TSD	TOILE SOLAIRE DOUBLE
TSM	MOTORIZED ROLLER SHADE
TYP	TYPICAL
V...	GLASS (TYPE...)
VO	OPERABLE SHUTTER

Aéroports de Montréal

location map



DA0006-A TEMPORARY PIER

project team

PROCHAINE DESTINATION

PRELIMINARY

NOTE: The plan or plans are provided by YUL (ADM) for indicative purposes only. YUL (ADM) cannot guarantee their accuracy so that the recipient must use them with reservation: it is his responsibility to verify the content and perform the appropriate additional surveys.

THESE DOCUMENTS MUST NOT BE USED FOR CONSTRUCTION PURPOSES

sceaux

no.	date	revisions
C	2025.10.31	APPEL D'OFFRES - LOT JT-14-01 - ASCENCEURS - AVANCEMENT 25%
B	2025.10.24	PRELIMINARY DEVELOPMENT
A	2025.10.18	AVANCEMENT 15%

YUL Aéroport International Montréal-Trudeau

project title

TEMPORARY PIER AT YUL AIRPORT
MONTRÉAL-TRUDEAU INTERNATIONAL

drawing title

NOTES AND LEGENDS

scale: 1 : 100

designed by: CN	date: 2025.10.31
drawn by: GA	project no.: DA0006
verified by: MF / AS / NR	reference(s): JLP 4371 | MSDL 25000 | Corgan #25021
	sheet: 485-A-001

Q142YXXXXAXXXX

2025-1

Size: Arch E - 1422 x 841